



# versatile™ 4C Mailbox, 15 High Suite



Floor




Floor

**NOTES:**

**1. Below are the USPS STD-4C installation guidelines:**

- a. At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
- b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
- c. No patron (tenant) lock shall be positioned more than 67" AFF.
- d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
- e. The USPS Arrow lock shall be positioned 36" - 48" AFF.

2. Modules noted with \* do not meet USPS STD-4C guidelines above.

PRODUCT SERIES: versatile™ 4C Mailbox 15 High Suite			
 <p>5935 Corporate Drive • Manhattan, KS 66503 www.florencemailboxes.com • (800) 275-1747 A GIBRALTAR INDUSTRIES COMPANY</p>	MODEL 4C15H	REV A	
	SCALE NONE	LAST REV DATE 5/15/2014	
	DRAWING NUMBER 4C15HCS	DRAWN BY AFD	SHEET 1 OF 1