


versatile™ 4C Mailbox, 4C08D-13



COMPARTMENT CHART

| DESCRIPTION | COMPARTMENT | COMPARTMENT SIZE | QTY. |
|---------------|-------------|-----------------------|------|
| MAILBOX | MB1 | 3" H x 12" W x 15" D | 13 |
| OUTGOING MAIL | OM3 | 10" H x 12" W x 15" D | 1 |

Notes:

- This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
 - At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
 - No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - No patron (tenant) lock shall be positioned more than 67" AFF.
 - No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - The USPS Arrow lock shall be positioned 36"- 48" AFF.
- This 4C mailbox can also be used for private applications.
- The rough opening width for multi-unit 4C installations is provided using the Florence configurator: www.florencemailboxes.com/configurator.

PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX

FLORENCE
CORPORATION

5935 Corporate Drive • Manhattan, KS 66503
800.275.1747 • www.florencemailboxes.com

| | |
|---------------------------|-------------------------|
| MODEL 4C08D-13 | REV C |
| SCALE NONE | LAST REV DATE 707/01/19 |
| DRAWING NUMBER 4C08D-13CS | DRAWN BY RAK |